

**SREE CHITRA TIRUNAL INSTITUTE FOR MEDICAL SCIENCES & TECHNOLOGY****THIRUVANANTHAPURAM—695 011, INDIA.**

(An Institute of National Importance under Govt.of India)

Phone—(91)0471—2443152,2524444 Fax—(91)0471—2446433, 2550728

Email-sct@sctimst.ac.in Web site—www.sctimst.ac.in

No.DCE(G)...610/DCE/2019/263

11.12.2019

**TENDER NOTICE**

(Minor Air conditioning duct Installation works)

Sealed quotations are invited from HVAC contractors having adequate experience and credentials for similar nature of work. Work Details are given below:

Sl.No :	Details of Work	Unit	Quantity	Rate	Amount
1	Supply, installation, balancing and commissioning of factory fabricated GSS sheet metal rectangular/round ducting with supports as per SMACNA complete with neoprene rubber gaskets, elbows, splitter dampers, vanes, hangers, supports etc.as per approved drawings and specifications of following gauges:-				
1.1	24 Gauge (Thickness 0.63mm)	SQM	32		
2	Supply, installation, testing and commissioning of GI Volume control manually operated duct damper complete with neoprene rubber gasket, nuts, bolts, screw linkages ,flanges etc., as per specifications.(Suitable for 1500 CFM air flow)	NO	2		
3	Supplying & fixing of powder coated extruded aluminum Supply Air Grills with aluminum volume control dampers as per specifications.	NO	2		
4	Supplying & fixing of powder coated extruded aluminum Return Air Grills with louvers but without volume control dampers complete as required.	NO	2		
5	Supplying and fixing of following thickness of mat finish, closed cell Nitrile rubber(Class“O”)insulation on duct after applying suitable adhesive for Nitrile rubber. The joints shall be sealed with 50mm wide and 3mm thick self adhesive nitrile rubber tape insulation complete as per specifications and as required.				
5.1	13mm Thickness	SQM	35		
6.1	Core Cutting :-Wall cutting(Thickness less than 0.5m) opening and making good the same for air duct and finishing.	SQM	0.5		
6.2	Core cutting :-Floor cutting (Thickness less than 0.5m) opening and making good the same for air duct and finishing.	SQM	0.5		
<b>Total Amount including all taxes</b>					

Note: Rate quoted should be inclusive of all material cost, labor cost service charges etc. Rate shall be quoted after inspecting the site. Location-MRI Ups room and CT Ups room. Period of completion will be 7 days from the date of work order. For details contact DCE-0471-2524211.

**Last Date and Time for Submission of sealed quotations: 20-12-2019 up to 03:00 pm.****Bid opening date and time: 20-12-2019- 03:30pm**